



Date: **May 29, 2026**  
Project: **Napaskiak Distribution Upgrade**  
Solicitation No.: **ITB 26081**  
Addendum No.: **02**

**TO ALL PLAN HOLDERS:**

The following changes, additions, clarifications, and/or deletions are hereby made part of the ITB Documents for the above noted project, as if fully contained therein. All other terms, conditions, and specifications of the original Invitation to Bid remain unchanged.

**Bidders must acknowledge receipt of this Addendum by email prior to the bid due date and time.**

The ITB Package is hereby clarified, changed or modified by the following:

**CONTRACT PROVISIONS AND SPECIFICATIONS**

The ITB Due date and time of June 17, 2026, at 2:00 PM AKST remains unchanged.

## QUESTIONS AND ANSWERS:

1. **Question:** What is to be done with the old transformers?  
**Answer:** The old transformers are to be turned over to the utility for use as spares and placed in a location designated by the utility.
2. **Question:** Is Additive Alternate #3 the only bid item that has new primary?  
**Answer:** Yes.
3. **Question:** Where poles are to be re-set do they have to be set in a new hole or can they be straightened in place?  
**Answer:** Existing poles can be straightened in place as long as they are straight and solid with compacted gravel backfill.
4. **Question:** Can we get details for anchor F3.10?  
**Answer:** Install F3.10 in accordance with the RUS standard detail using gravel backfill.
5. **Question:** Is new mounting hardware required for all transformer replacements?  
**Answer:** Yes.
6. **Question:** Are new grounding loops and cutouts required for all transformer replacements?  
**Answer:** Yes.
7. **Question:** Is there a local gravel source in Napaskiak?  
**Answer:** No. Gravel will need to be imported.

**END OF ADDENDUM #02**