

April 3, 2015



Addendum 2
Invitation to Bid 15113
Construction Rural Power Systems Upgrade
On behalf of the City of Akiak

Addendum 2 is issued to clarify disposal of existing transformers to be retired:

1. **No Change.** Bidders shall submit sealed bids in single (1) copy. All Bids including any modifications or withdrawals shall be received prior to the bid opening; bids will be publically opened at Authority's Office on **April 9, 2015 at 2:00p.m.** Alaska time, Willow Conference Room.
2. Please acknowledge receipt of this addendum on the Bid Schedule.
3. **ADD** paragraph: Specification Section 16300, paragraph 3.01.C as follows:

"C. Disposal of Liquid Dielectrics

The Contractor shall be responsible for sampling and performing PCB testing on all transformers to be retired, to determine if they contain PCBs that require special handling for disposal. PCB-contaminated dielectrics must be marked as PCB and transported to and incinerated by an approved EPA waste disposal facility. The Contractor shall furnish certification of proper disposal. Contaminated dielectrics shall not be diluted to lower the contamination level. The cost for this special handling shall be incidental to the construction contract up to (5) five transformers. If in excess of (5) five transformers require special handling for disposal, the contractor shall address the additional costs according to Section 00700 General Conditions. All other transformers shall be disposed of as indicated on the drawings and elsewhere in the specifications."

4. **REPLACE** paragraph: Specification Section 16400, paragraph 3.01.C in its entirety as follows:

"C. Disposal of Liquid Dielectrics

The Contractor shall be responsible for sampling and performing PCB testing on all transformers to be retired, to determine if they contain PCBs that require special handling for disposal. PCB-contaminated dielectrics must be marked as PCB and transported to and incinerated by an approved EPA waste disposal facility. The Contractor shall furnish certification of proper disposal. Contaminated dielectrics shall not be diluted to lower the contamination level. The cost for this special handling shall be incidental to the construction contract up to (5) five transformers. If in excess of (5) five

transformers require special handling for disposal, the contractor shall address the additional costs according to Section 00700 General Conditions. All other transformers shall be disposed of as indicated on the drawings and elsewhere in the specifications.”

Thank you for your interest in our bid requirements.

Regards,

Rich Wooten, CDT, Contract Compliance Specialist
rwooten@aidea.org